



Notes: 6 mil poly must be placed on grade prior to Paraseal LG. All seams overlapped 4" taped with Permanent Seam Tape. Paraseal products require a minimum of 24 psf compaction/confinement to be effective.

This detail is intended for conceptual purposes only. Detail must be reviewed by a project/design professional. See [www.tremcosealants.com](http://www.tremcosealants.com) for the most up-to-date product information.

Rev	Date	Description	By
1	10/10/2013	Update Detail	KAB



www.tremcosealants.com  
 3735 Green Road \* Beachwood, OH 44122  
 Phone : 866-209-2404 \* Fax: 216-766-5535

Project: Below Slab-on-Grade  
 Detail: Termination at Floor to Interior Wall Face - HDPE Side Up

Drawn by: KT      Checked by: WH      Scale: None

Sheet Number:  
 Date: 8/26/2009

File Name:  
 10861

Rev #  
 1