

12" X 12" DETAIL STRIP OF PARASEAL LG AT CORNERS

SUPERSTOP

PARASEAL LG BELOW FLOOR AND FOOTING (SEE BELOW SLAB ON GRADE DETAILS)

PARASEAL MEMBRANE WITH HDPE SIDE FACING INSTALLER

2" PARAGRANULAR CANT

4"

REFER TO OUTSIDE CORNER DETAIL

12"

NOTE: PARASEAL PRODUCTS REQUIRE A MIN 24 PSF OF COMPACTION/CONFINEMENT IN ORDER TO FUNCTION AS DESIGNED

The architecture, engineering, and design of the project using the Tremco products are the responsibility of the project's design professional. All products and systems must comply with local building codes and standards. This detail is for general information and guidance only and Tremco specifically disclaims any liability for the use of this detail. The project design professional determines, in its sole discretion, whether this detail or a functionally equivalent detail is best suited for the project. This detail is subject to change without notice. Contact Tremco to ensure you have the most recent version.

Paraseal Backfilled Walls

Detail: Below Slab on Grade to Backfilled Wall Transition

File Name:

Drawn by: KAB

Checked by: WH

Scale: NTS

Date: 2/23/2022

BFW-P-T-02



Tremco Technical Support: 866-209-2404

www.tremcocpg.com



Construction Products Group